

May 9th, 2016

To: Planholders of S.A.P. 042-610-039, S.A.P. 042-624-016

## **ADDENDUM #2**

**Additional provisions have been added to S-29 – (2105) SALVAGED AGGREGATE BASE STOCKPILED and S-32 – (2211) AGGREGATE BASE CLASS 5 MOD.**

Please find attached the amended proposal sheet for the above mentioned projects:


**Proposal Sheet Number: 11-S**

Amended proposal sheet may be downloaded from the Lyon County Website Highway Bid Lettings page at

<http://www.lyonco.org/bid-lettings/230-highway-2016-bid-lettings/711-notice-to-contractors-sap-42-610-039-and-sap-42-624-016>

Please call our office if you have any questions concerning this Addendum.

Sincerely,



Aaron VanMoer, PE  
Lyon County Project Engineer

S-29.1 Salvage the pulverized bituminous surface and underlying aggregate base as directed by the engineer. Bituminous and aggregate thickness shown on the plans are approximate, actual thickness and quantities may vary.

S-29.2 All materials to be stockpiled shall be screened or crushed to pass the 2" sieve prior to being placed in stockpiles.

S-29.3 Stockpiles shall not be placed in areas that may damper drainage.

S-29.4 The contractor shall be responsible for location and restoration of stockpile sites.

S-29.5 **Final payment shall be verified by weigh tickets required for item 2105.609 – SALVAGED AGGREGATE BASE PLACED FROM STOCKPILE.**

**S-30 (2111) TEST ROLLING**

The provisions of 2211 are supplemented by the following:

S-30.1 **Provide and test with a TR30 pneumatic tire test roller as described in MnDOT 2111.**

**S-31 (2123) 1.5 CU YD BACKHOE**

The provisions of 2123.610 are supplemented by the following:

S-31.1 Hours shall be provide to located existing tile line locations or other work as directed by the engineer. If the contractor elects to use a larger backhoe than specified it shall be at the expense of the contractor.

**S-32 (2211) AGGREGATE BASE CLASS 5 MOD**

Aggregate base courses shall be constructed in accordance with the provisions of MnDOT 2211 except as modified below:

S-32.1 Compaction shall be achieved by the "Quality Compaction Method" described in MnDot 2211.3D2.

S-32.2 **Aggregate Base Class 5 MOD (2221.501) is modified so 6%-12% shall pass the #200 sieve.**

**S-33 (2215) FULL DEPTH RECLAMATION**

The provisions of 2215.604 are as follows:

S-33.1 Pulverize existing bituminous surface with a self-propelled reclaiming machine with the ability to uniformly pulverize the pavement and underlying layer to the specified depth or as directed by the engineer. Pulverized bituminous and underlying aggregate base shall produce a uniformly mixed aggregate base.

S-33.2 Full depth reclamation shall be a single operation. The engineer will measure the reclamation area by the square yard.

**ADDENDUM #2**

**S.A.P. 042-610-039 & S.A.P. 042-624-016**

**CONFIRMATION OF RECEIPT**

COMPANY NAME: \_\_\_\_\_

SIGNATURE: \_\_\_\_\_

PLEASE FAX TO 507-532-8217 or Email to NancyBoogaard@co.lyon.mn.us